

Completed Restoration Projects

Friends Pond

(Bynum Run Watershed)

Completed 2011

This project involved the repair of the dam embankment, construction of an emergency spillway and the installation of an aquatic bench for marsh plantings, a safety bench, a paved trail and timber boardwalk.

Bynum Ridge Stream Stabilization

(Bynum Run Watershed)

Completed 2011

A section of Bynum Run within the Bynum Ridge subdivision was experiencing bank erosion causing the failure of previously-constructed concrete bank revetments. This project removed the old revetments and replaced them with imbricated riprap, coir fiber logs and vegetative plantings. These techniques provide water quality and habitat value as well as providing bank stability.

Hickory Elementary School Rain Garden

(Deer Creek Watershed)

Completed 2011

A rain garden was constructed to treat stormwater runoff from a school parking lot. Each student in the school participated in planting the native vegetation and flowers.

Forest Hill Elementary School Rain Garden

(Deer Creek Watershed)

Completed 2011

Several rain gardens were constructed to treat stormwater runoff from the parking lots. Gifted and Talented students helped with the design of the gardens and every student in the school participated in planting the native vegetation and flowers.

Plumtree Run at Tollgate Road Stream Restoration

(Plumtree Run Watershed)

Completed 2011

This project involved the restoration of 2000 linear feet of the mainstem of Plumtree Run. Structural measures included stone toe protection, imbricated rip rap and step pool structures. The project also included fencing to minimize livestock access, two constructed wetlands and stream buffer plantings.

Abingdon Library

(Winters Run Watershed)

Completed 2010

A rain garden was constructed adjacent to the parking lot to treat stormwater runoff from the library roof.

Laurel Valley Stream Restoration
(Bynum Run Watershed)

Completed 2009

Approximately 1,200 linear feet of eroded stream channel was restored utilizing structural measures including imbricated rip rap, stone toe protection, log drop structures and rock weirs. Trees and shrubs were planted in the riparian buffer.

Plumtree Run Invasive Species Management
(Plumtree Run Watershed)

Completed 2009

Invasive plant species were removed along 1000 linear feet of Plumtree Run downstream of Tollgate Rd. This project involved three consecutive years of chemical and mechanical removal of invasive species in the riparian buffer, in preparation for a stream restoration project.

Laurel Valley Stormwater Retrofit
(Bynum Run Watershed)

Completed 2005

An existing recreational pond in the Laurel Valley subdivision was modified to temporarily store stormflow and release the water more gradually into the receiving stream. Additionally, trees and shrubs were planted around the perimeter of the pond to improve pollutant uptake from overland flow and a forebay was added to trap sediment entering the pond.

Laurel Valley Bioretention
(Bynum Run Watershed)

Completed 2005

A triple-cell bioretention facility was constructed in the Laurel Valley subdivision open space. This facility treats a portion of the stormwater from the stormdrain system as well as overland flow.

Harford Center Pocket Wetland
(Swan Creek Watershed)

Completed 2004

A small shallow wetland was constructed at the intersection of MD Rt 155 and Earleton Rd. The wetland treats runoff from Rt 155 before discharging to an ephemeral stream.

Harford Center Bioretention
(Swan Creek Watershed)

Completed 2004

A two-celled bioretention system was constructed on the Harford Center property in Havre de Grace. The bioretention treats runoff generated by the parking lot. In addition, an asphalt path, a bridge and benches were constructed to allow wheelchair access for the clients of Harford Center.

Box Hill – South Tributary Stream Restoration
(Bynum Run Watershed)

Completed October 2003

This project involved the restoration of 1,100 linear feet of a tributary to Bynum Run on the south side of the Box Hill North subdivision. The stream was experiencing downcutting and widening as a result of uncontrolled stormwater runoff. The banks and stream bed were stabilized using a variety of techniques such as step-pools, rock weirs and imbricated riprap.

Haverhill Channel Stabilization
(Foster Branch Watershed)

Completed 2003

A severely eroding drainage channel in Joppatowne was stabilized using a series of gabion drop structures. Prior to stabilization, the eroding 725 linear foot drainage channel was a significant source of sediment to Foster Branch.

Mt Royal Stream Restoration
(Swan Creek Watershed)

Completed 2002

An unnamed tributary of Swan Creek, located on Aberdeen Middle School property was restored through the use of channel and bank grading, rock weirs and coir fiber rolls. The project is located immediately downstream of a constructed shallow marsh.

Stillmeadow Channel Stabilization
(Foster Branch Watershed)

Completed 2001

This unnamed tributary to Foster Branch had a significant channel headcut at a stormdrain outfall and spot erosion at outside bends of the channel. This project involved the construction of a drop manhole at the stormdrain outfall and installation of crib walls and toe protection at the eroding bends.

Mt Royal Shallow Marsh
(Swan Creek Watershed)

Completed 2001

A shallow marsh was constructed on the Aberdeen Middle School property. The marsh treats uncontrolled stormwater from a medium-density residential development and from MD Rt 22.